



PCiRoads

14123 42nd Street NE
St. Michael, MN 55376-9564

Telephone: 763.497.6100 / Fax: 763.497.6101
pciroads.com

To: Subcontractors and Suppliers

From: PCiRoads, LLC

Nicollet County
SAP 052-613-021 CSAH 13
Bids: 04/19/2021

PCiRoads, LLC will be bidding on the reference project and is requesting quotes for all available work. Please see attached sheet for details.

All or any part of the bid items will be accepted and considered for the project. All quotes should include all incidental items except as noted on your quote. We are prepared to assist you in project scheduling, preparing proposals, pit and batch plant locations, interpreting plans and specifications, bonding and insurance needs, and any other areas you may have questions. Please note on your quote whether items are tied or not. Also, please include line number, description, quantity and unit price for each item as well as a grand total. Please contact Kim Michels, 763-497-6100 or kmichels@pciroads.com with any questions. Plans are available from www.questcdn.com #7690007 or you may contact me.

Thank you,

Kim Michels
PCiRoads

Schedule of Prices

No.	Mat No.	Item	Units	Quantity	Unit Price	Total Price
1	2011.601	CONSTRUCTION SURVEYING	LS	1		0.00
2	2021.501	MOBILIZATION	LS	1		0.00
3	2051.501	MAINT & RESTORATION OF HAUL ROADS	LS	1		0.00
4	2104.502	REMOVE MAIL BOX SUPPORT	EACH	20		0.00
5	2104.502	SALVAGE MAIL BOX SUPPORT	EACH	6		0.00
6	2104.503	REMOVE CABLE GUARDRAIL	L F	200		0.00
7	2104.504	REMOVE BITUMINOUS SHOULDER PAVEMENT	S Y	4000		0.00
8	2221.509	SHOULDER BASE AGGREGATE CLASS 1	TON	1900		0.00
9	2231.508	MIXTURE FOR JOINTS & CRACKS	LB	21000		0.00
10	2232.504	MILL BITUMINOUS SURFACE (2.5")	S Y	84506		0.00
11	2232.603	MILLED SINUSOIDAL RUMBLE STR CONC-INTERM	L F	48647		0.00
12	2301.502	DOWEL BAR	EACH	29624		0.00
13	2301.504	PLACE CONCRETE PAVEMENT 7" (P)	S Y	83478		0.00
14	2301.507	STRUCTURAL CONCRETE	C Y	18785		0.00
15	2301.508	SUPPLEMENTAL PAVEMENT REINFORCEMENT	LB	10368		0.00
16	2360.509	TYPE SP 9.5 WEARING COURSE MIX (3;B)	TON	9700		0.00
17	2540.602	INSTALL MAIL BOX SUPPORT	EACH	6		0.00
18	2540.602	MAIL BOX SUPPORT	EACH	20		0.00
19	2540.602	RELOCATE MAIL BOX SUPPORT	EACH	26		0.00
20	2554.502	END TREATMENT-TANGENT TERMINAL	EACH	2		0.00
21	2554.503	TRAFFIC BARRIER DESIGN TYPE 31	L F	200		0.00

22	2563.601	TRAFFIC CONTROL SUPERVISOR	LS	1		0.00
23	2563.601	TRAFFIC CONTROL	LS	1		0.00
24	2574.505	SOIL BED PREPARATION	ACRE	5.2		0.00
25	2574.507	COMMON TOPSOIL BORROW	C Y	2500		0.00
26	2574.508	FERTILIZER TYPE 3	LB	1100		0.00
27	2575.505	SEEDING	ACRE	5.2		0.00
28	2575.508	SEED MIXTURE 25-131	LB	1150		0.00
29	2575.508	HYDRAULIC REINFORCED FIBER MATRIX	LB	20300		0.00
30	2582.503	4" SOLID LINE MULTI COMP GR IN (WR)	L F	16324		0.00
31	2582.503	6" SOLID LINE MULTI COMP GR IN (WR)	L F	55870		0.00
32	2582.503	4" BROKEN LINE MULTI COMP GR IN (WR)	L F	4940		0.00

GRAND TOTAL BID \$ 0.00